BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work:Excavation of Temporary Immersion Tank for Lord Ganesh Idols at Doddabommasandra Lake in Ward No. 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	25.20	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	184.73	Rupees One Hundred Eighty Four and Seventy Two Paise Only
2	187.50	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	222.38	Rupees Two Hundred Twenty Two and Thirty Seven Paise Only
	187.50	Above 1.5 Mtrs Depth Add 25% Extra	Cum	277.97	Rupees Two Hundred Seventy Seven and Ninety Seven Paise Only
3	820.00	Code 0516 - Providing Plastic Sheet etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	6.66	Rupees Six and Sixty Six Paise Only
4	165.00	Supply of water Through water Tank for filling Tank etc., complete and as per the directions of the Engineer-in-charge of the work	Each	360.00	Rupees Three Hundred Sixty Only
5	2.50	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	888.00	Rupees Eight Hundred Eighty Eight Only
6	66.00	Hire charge of pumping water 3.5 KL/hr capacity Pump etc., complete and as per the directions of the Engineer-in-charge of the work	Hrs	55.50	Rupees Fifty Five and Fifty Paise Only
7	165.00	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc., complete and as per the directions of the Engineer-in-charge of the work	Days	287.36	Rupees Two Hundred Eighty Seven and Thirty Five Paise Only

8	480.00	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis etc., complete and as per the directions of the Engineer-in-charge of the work	Mtrs	65.00	Rupees Sixty Five Only
9	13200.00	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc., complete and as per the directions of the Engineer-in-charge of the work	Sft	8.00	Rupees Eight Only
10	165	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc., complete and as per the directions of the Engineer-in-charge of the work	Rft	17.00	Rupees Seventeen Only
11	220	Hire Charge for Armless Plastic Chairs etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	4.00	Rupees Four Only
12	110.00	Hire Charge for Wooden Table of Size 6ft x 2ft etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	40.00	Rupees Forty Only
13	1100	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire etc., complete and as per the directions of the Engineer-in-charge of the work	Mtrs	9.00	Rupees Nine Only
14	66.00	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling etc., complete and as per the directions of the Engineer-in-charge of the work	Hrs	699.30	Rupees Six Hundred Ninety Nine and Thirty Paise Only
15	88	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	285.00	Rupees Two Hundred Eighty Five Only
16	5	Hire charges compoment name 1087 Crane charges etc., complete and as per the directions of the Engineer-in-charge of the work	Day	4440.00	
17	328.90	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	89.42	Rupees Eighty Nine and Forty Two Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Yelahanka Zone
Bangalore Mahanagara
Bangalore 92